



## **City of Zephyrhills Site Plan Review Committee**

**Tuesday, May 18, 2021**

Council Chambers, City Hall  
5335 8th Street, Zephyrhills, FL 33542  
9:30 AM

**Pursuant to Executive Order No. 20-69 by the Office of Governor Ron DeSantis on March 20, 2020, municipalities may conduct meetings of their governing boards without having a quorum of its members present physically or at any specific location, and utilizing communications media technology such as telephonic or video conferencing, as provided by Section 120.54(b)2, Florida Statutes.**

The City of Zephyrhills will hold hybrid in-person and communications media technology public meetings using GoToMeeting to allow Council Members, Board/Committee Members, Mayor, City Staff, and the public to attend remotely.

**Please Join the GoToMeeting:**

+1 (872) 240-3412  
Access Code: 752-990-805  
<https://global.gotomeeting.com/install/752990805>

*Please mute your phone/computer unless you wish to speak to specific item.*

### **1. PLAN ITEMS**

- 1.I. SUB-007-21  
Lot Split/Certified Parcel Subdivision - 04-26-21-0020-00000-00AA - Home Pro of Central|Southwest Florida - Request to subdivide approximately 0.37 acres of vacant land generally located at 6554 Brentwood Drive in Silver Oaks into 2 separate lots - Zoned PUD.
- 1.II. SUB-0005-20  
Platted Subdivision - Zephyr Lakes Phase 4B - (a portion of 35-25-21-0010-00500-0000) - Phase 4B Plat of the Zephyr Lakes PUD submitted by DUNE FL LAND I SUB LLC.
- 1.III. SPR-0022-21  
Site Development/Construction Plan Submittal - Trotter's Crossing (27-25-21-0010-00300-0000 and 27-25-21-0030-04900-0000) - Wareco II, LLC - Site Development/Construction Plans submitted for Trotter's Crossing, generally located on the west side of US Hwy 301, north of Phelps Road.
- 1.IV. ANX/FLU/RZ-0005-21  
ANNEXATION; SMALL-SCALE COMPREHENSIVE PLAN AMENDMENT; ZONING AMENDMENT (SIMULTANEOUS REVIEW) - Terrace at Pretty Pond - Michael Mann (Applicant) - Petition to Annex approximately 1.75 acres of Real Property generally

located at the Southeast Corner of Pretty Pond Road and Wire Road (35-25-21-0010-06800-0010); Small-Scale Comprehensive Plan Amendment to the Future Land Use Map changing the designation from Pasco County RES-6 (Residential, 6 DU/GA) to City RU (Residential Urban, 20 DU/GA) for 1.75 acres of real property (35-25-21-0010-06800-0010); Small-Scale Comprehensive Plan Amendment to the Future Land Use Map changing the designation from City RE (Residential Estate, 2 DU/GA) to City RU (Residential Urban, 20 DU/GA) of approximately 2.06 acres of Real Property located at 38510 Pretty Pond Road (35-25-21-0010-06800-0000); Rezoning request from County AR (Agricultural) to City R4 (Multi-Family Residential) for 1.75 acres of Real Property (35-25-21-0010-06800-0010); and Rezoning request from City ER (Estate Residential) to City R4 (Multi-Family Residential) for 2.06 acres of Real Property (35-25-21-0010-06800-0000) for the development of approximately 49 townhome units (~13 DU/Acre)

1.V. FLU/RZ-0003-21

SMALL-SCALE COMPREHENSIVE PLAN AMENDMENT & ZONING AMENDMENT - Autumn Palm Villas - Autumn Palm Villas, LLC - A Small-Scale Comprehensive Plan Amendment to the Future Land Use Map from RS (Residential Suburban, 7.5 DU/GA) to RU (Residential Urban (20 DU/GA); and Rezoning Request from R3 (Medium-Density Residential) to R4 (Multi-Family Residential) on Approximately 9.82 acres of Real Property generally located at the Southwest Corner of Autumn Palm Drive and Vinson Avenue to allow the development of approximately 94 townhome dwelling units (9.57 DU/Acre).

Documents:

[RZFLU003-21\\_APPLICATION REPORT.PDF](#)

[RZFLU003-21\\_LAYOUT PLAN.PDF](#)

[RZFLU003-21\\_MAPS.PDF](#)

# Autumn Palm Villas

Future Land Use Plan Amendment  
& Rezoning Application

## TABLE OF CONTENTS

April 22, 2021

Prepared for:

Robert Chalfin, CPA  
Autumn Palm Drive, LLC  
Metuchen, NJ

Prepared by:

**Susan Swift, AICP**  
Colliers Engineering & Design

5471 W. Waters Avenue, Suite 100  
Tampa, Florida 33634  
Main: 813 582 4652  
Colliersengineering.com

## Autumn Palm Villas

### TAB 1. APPLICATION FORM

### TAB 2. PROJECT DESCRIPTION & JUSTIFICATION

Project Description  
Proposed Development  
Existing Site Conditions  
Surrounding Development Pattern  
Comprehensive Plan  
Rezoning  
Public Facilities  
Potable Water  
Wastewater  
Stormwater  
Solid Waste  
Schools  
Fire Protection/EMS  
Law Enforcement  
Recreation  
Zephyrhills Municipal Airport  
Justification.  
Consistent with Comprehensive Plan  
Compatibility with Surrounding Area & Development Pattern  
Compliance with LDRs  
Suitability & Premature Development Analysis  
Maps  
Location Map  
Aerial  
Current Future Land Use Map  
Current Zoning Map

### TAB 3. APPLICATION MATERIALS

Proof of Ownership  
Boundary Survey and Legal Description  
Surrounding Property Owners List and Envelopes  
Environmental Report - previously provided  
Historic/Archeological Report - Not Required  
Traffic Study - previously provided

## Autumn Palm Villas

### Project Description

#### Proposed Development

The property owner, Autumn Palm Drive, LLC is applying for a Future Land Use Plan Amendment and a Rezoning for this site in order to clarify the entitlements for a site plan that has been approved by the City of Zephyrhills. The site plan was approved on September 21, 2020 for 84 townhomes on a 9.82 acre site at the southwest corner of Autumn Palm Drive and Vinson Avenue. This is a combined application to adjust the future land use designation from Residential Suburban (RS) to Residential Urban (RU) and rezone the property from R-3 to R-4.

The site plan was approved under the R-3 conventional zoning district for attached single-family units on 2,100 SF lots. Each of the eleven structures contains eight units, with one structure containing only six units, for a total of 84 units. Access is on Autumn Palm Drive and the project is designed around a U-shaped road which ends in a cul-de-sac but offers a second (emergency) access onto Autumn Palm Drive. Three parks will be provided as well as sidewalks along Autumn Palm Drive and internal to the site. Parking is provided for each unit in individual garages and driveways.

The City approved the site plan using the Provisional Level 1 Review for Attached single-family units as shown on the Use Table, and the 10.5 units/acre density for duplexes per Section 2.01.03.05. Despite the overlapping terminology, however, the Residential Suburban classification is limited to 7.5 units per acre.

This application for a map amendment and rezoning are intended to align the density and the unit type due to differing interpretations of plan consistency. The RU land use allows the higher density and the R-4 allows townhouse units without a provisional approval or administrative interpretation.

#### Existing Site Conditions

The 9.82-acre site is currently vacant with Pine-Mesic Oak upland across the site and there are no wetlands. According to the report prepared by Pacscon on October 22, 2019, there are no protected or endangered species with the exception of two active and several inactive gopher tortoise burrows which will be relocated according to the mitigation plan and permits approved by the Florida Fish and Wildlife Commission.

According to FIRM Map # 12101C0452F, the flood zone is "X" and the topography is generally flat. The site contains minimal groundcover and there is a pedestrian/vehicular dirt road around its perimeter. The soils within the project area have been mapped as Tavares sand, 0 to 5 percent slopes (06). Vegetation within the site primarily includes *Quercus virginiana* (live oak), *Quercus laurifolia* (laurel oak), *Quercus nigra* (water oak), *Quercus geminata* (sand live oak), *Pinus elliottii* (slash pine), *Cinnamomum camphora* (camphor tree), *Serenoa repens* (saw palmetto), *Nephrolepis exaltata* (sword fern), *Callicarpa americana* (beautyberry), and *Solanum laxum* (potato vine).

Autumn Run Drive is an asphalt two-lane County roadway with 60 ft. right-of-way. Access to shopping and community services is provided via this 1.2 mile neighborhood street connecting C Avenue to the north and Chancey Road to the south which provides a direct route to U.S. 41/301/Gall Boulevard which is just 0.4 miles from Autumn Palm Dr.


Water, sewer and solid waste facilities are provided by the City of Zephyrhills Utilities Department. Public safety services are provided by the Zephyrhills Police Department and Pasco County now provides fire and EMS services.

### Surrounding Development Patterns

The subject site is the only vacant site in the area – and has residential development surrounding it. This particular acreage was annexed into the City in 2005 and all abutting properties lie within unincorporated Pasco County, primarily zoned for mobile homes. The site to the northwest corner of this project is within the city limits and recently completed construction of a similar community under the Residential Urban category, Walnut Grove. The surrounding neighborhood is similar in density to the requested rezoning, as shown below.

	Current Use	Future Land Use Map	Zoning District
<b>North</b>	Mobile homes	Residential-9	RMH
<b>South</b>	Single-family homes	Residential-9	R1 MH
<b>East</b>	Mobile homes	Residential-9	RMH
<b>West</b>	Single-family homes	Residential-9	AR & R-3

*Note: all abutting properties shown above are in unincorporated Pasco County*



## Comprehensive Plan

The Zephyrhills Comprehensive Plan policies are focused on the protection of neighborhoods and follow a land use model of Village Centers and Neighborhoods. The current Future Land Use Map classification for the subject site is Residential Suburban (RS) which provides a density range of 2.5-7.5 dwelling units per gross acre. Such properties should be well-suited for residential uses that are consistent with suburban, non-intensive qualities and natural resources.

The RU classification is being requested to recognize the more intense densities of surrounding properties in this area and the proposed Autumn Run development. The site connects to the city limits at the northeast and northwest corners. However, the properties abutting the property are not in the city limits and are regulated by the Pasco County Land Use Map and zoning regulations. As shown in the table, above, are classified as Residential-9 (9 units per acre) which is much more consistent with the proposed RU densities which range from 7.5-14 dwelling units per gross acre. The Residential Urban (RU) classification is intended for low to moderately intensive residential development and "accommodates a mix of higher density single family and multi-family uses and highly compatible retail and office uses."

## Zoning

The applicant is requesting a rezoning from R-3 (Medium Density Residential) to R-4 (Multi-family Residential). The code describes the purpose and intent of these two districts as follows:

*§ 2.01.03.05 MEDIUM DENSITY RESIDENTIAL (R-3). This category is established to identify areas of the city appropriate for medium density mixed single-family and duplex development. The maximum density shall be seven single-family detached or 10.5 duplex dwelling units per gross acre with a maximum of 60% impervious area.*

*§ 2.01.03.06 MULTI-FAMILY RESIDENTIAL (R-4). This category is established to identify areas of the city appropriate for higher density mixed duplex and multi-family residential development. The maximum density of development shall be 20 units per gross acre with a maximum of 75% impervious area.*

In addition, the Land Development Code (LDC) includes several definitions of residential unit types but does not define "attached units" which is the term used in the guidelines for townhouses in Section 2.01.03.06.01 of the LDC. This may create confusion about which unit types and densities are intended in each Future Land Use classification. As a result, this application seeks to align the Future Land Use Map and the most appropriate zoning district to Residential Urban and R-4 Multi-family Residential, respectively.

## Public Facilities

Potable Water. Potable water service is provided by the City of Zephyrhills. According to the City's Adequate Public Facilities Levels of Service (LOS), one residence utilizes 300 gallons of water per day, and the projected impacts of the change in land use and zoning are outlined below:

R-3: 9.82 acres X 10.5 units X 300 gallons per day = 30,933 gpd

R-4: 9.82 acres X 14 units X 300 gpd = 41,244 gpd  
 Potential increase: 10,311 gpd

Wastewater. Sanitary sewer service is provided by the City of Zephyrhills. As proposed, the project will provide a lift station compliant with city technical manuals. The impacts for the current vs. proposed zoning are analyzed based upon the LOS standard of 200 gallons per unit per day:

R-3: 9.82 acres X 10.5 units X 200 gallons per day = 20,622 gpd  
 R-4: 9.82 acres X 14 units X 200 gpd = 27,496 gpd

Solid Waste. The City's Solid Waste Department will provide waste collection for this project which will be disposed of at the Pasco County Resource Recovery Plant, per the Interlocal Agreement. Utilizing the Pasco County Level of Service (LOS) of 1.5 tons (3,000 lbs.) per year per dwelling unit. The comparison of the impacts is shown below. As one can see, the proposed development has less impact than the R-3 or R-4 zoning district maximum densities.

R-3: 9.82 acres X 10.5 u/a X 3000 lbs = 155 tons/year  
 R-4: 9.82 acres X 14 u/a X 3000 lbs = 206 tons/year

Stormwater. The proposed development will consist of stormwater retention areas to provide water quality treatment and attenuate stormwater to reduce discharge from the site. The site has been designed with stormwater ponds meeting city and water management district requirements. Schools. Students from this development will be assigned to these schools with the 2020 attendance shown:

Chester Taylor Elementary	102%
Raymond B. Stewart Middle School	95%
Zephyrhills High School	101%

Fire Protection/EMS. Recently, the City of Zephyrhills fire and EMS services were merged with the Pasco County Fire Rescue Department.

Law Enforcement. The site will be served by the City of Zephyrhills Police Department.

Recreation. Autumn Palm Villas is 9.82 acres in size and is dedicating three sites, totaling 0.717 acres on-site park and recreation space. In addition, the residents of Autumn Palm Villas will have several park and recreation facilities within three (3) miles:

- Zephyr Park 0.9 miles
- Shephard Park 1.1 miles
- Zephyrhills Skatepark 1.7 miles
- Zephyrhills Train Depot Museum 1.8 miles
- Zephyrhills Military Museum 1.8 miles
- Veterans Memorial Park 2.1 miles
- Gunner Paw Park 2.3 miles
- Samuel Pasco Recreation Center 2.9 miles  
 (County facility)

Zephyrhills Municipal Airport. According to the letter from the Federal Aviation Authority (FAA) dated January 19, 2020, "This aeronautical study revealed that the structure does not exceed obstruction standards and would not be a hazard to air navigation provided the conditions of the letter."

## Justification

### Consistent

This application is consistent with the Zephyrhills Comprehensive Plan. The plan strongly protects residential neighborhoods and is based upon the concept of Village Centers and Neighborhoods as its preferred land use model:

*"This concept is described simply in the following: picture a strong downtown as a magnet and housing as iron filings. The iron filings cluster around the magnet, densely close by and spreading out as their distance from the magnet increases, in what planners call a density gradient."*

As noted earlier, the Residential Urban (RU) accommodates a mix of higher density single family and multi-family uses. The density gradient for this location is more conducive to the Residential Urban land use classification which is intended for locations with transit, arterial and collector highways, and proximity to employment and shopping. The site is within a mile of downtown Zephyrhills, just a few blocks west of US Hwy 301, and between State Road 56 and State Road 54. Transit service is available nearby via the Route 30 and Route 41 Pasco County bus service. In addition, the RU classification is appropriate where recreational facilities are sufficient to serve the residents. There are five city parks, one county park and two museums within 2.3 miles of the subject site.

Finally, this application is consistent with the policies in the Comprehensive Plan including:

Objective LU-1-2: The integrity and quality of life will continue to be maintained in existing and future residential neighborhoods.

Policy LU-1-2-2: Existing residential areas shall be protected from incompatible activities. Other land uses shall also be protected from the encroachment of incompatible residential activities.

Policy LU-1-2-3: The location and extent of residential land uses shall be in accordance with the Future Land Use Map and the descriptions of types, sizes and densities of land uses contained in this element.

Policy LU 1-2-4: Land development shall take place in a manner that is compatible with the type and scale of surrounding land uses.

In addition to the policies in the Future Land Use Element, this plan amendment and rezoning application furthers policies in other parts of the Plan which call for new development in areas served by water, sewer and other infrastructure; and seek a variety of housing types for city residents (Policy HOU-1-1-2).

### **Compatible**

The site is compatible with the surrounding neighborhoods. The City recently approved the Walnut Groves townhomes across the street from this site, at a similar density. The site was annexed into Zephyrhills in 2005 and the other abutting properties are still under the jurisdiction of unincorporated Pasco County which has historically assigned a higher density for this area. The County's Comprehensive Plan is Residential – 9 on all abutting properties, and most are developed as mobile or modular homes. Therefore, the Residential Urban land use classification with a density of 7.5-14 units per acre, is more compatible with the surrounding area than the Residential Suburban density of 2.5-7.5 units per acre.

### **Compliant**

As noted above, a site plan was approved on September 21, 2020 and was deemed to be compliant with City and other applicable codes. Future changes, if any, would be required to comply with the Zephyrhills Comprehensive Plan and Land Development Code. In terms of adequate public facilities, it should be noted that the approved site plan of 84 units impacts the city's services at a much lower number than the maximum allowed by this application for RU land use and R-4 zoning. Based upon the levels of service used above, the Autumn Palm Villas would have only the following impacts:


- Water:  $84 \times 300 \text{ gpd} = 25,200 \text{ gpd}$
- Sewer:  $84 \times 200 \text{ gpd} = 16,800 \text{ gpd}$
- Solid Waste:  $84 \text{ units} \times 3000 \text{ lbs} = 126 \text{ tons/year}$

### **Suitability & Premature Development Analysis**

This nearly 10-acre site is highly suitable for townhouse development at the densities allowed in the Residential Urban (RU) land use classification and the R-4 Multi-residential zoning district. It is near US 301/SR 41 and between SR 54 and SR 56 which are east-west connections through the county. As required by the policies of the Zephyrhills Comprehensive Plan, the increased density is warranted by the proximity to downtown, to shopping and recreation facilities.

The subject site and the proposed development are compatible with the surrounding neighborhood and in fact, it is the only property that remains vacant. The surrounding properties are all developed as mobile homes or manufactured homes pursuant to the Pasco County Land Use Plan of 9 units per acre. It is served by adequate roads, parks and public facilities; and shopping and transit are nearby. Therefore, the development of this site will not be premature.


Finally, a site plan has been approved, showing compliance with all applicable codes and statutes. The site plan provides connection to city water and sewer services, provision of a lift station, new sidewalks and three park sites, in addition to compliance with townhouse provisions in the Land Development Code.



#### DEVELOPER/APPLICANT

AUTUMN PALM DRIVE, LLC  
45 BIRDS ESTATE  
METUCHEN, NJ 08840  
CONTACT: ROBERT CHALFIN  
PHONE: (732) 321-1099

THIS PROJECT MUST MEET THE REQUIREMENTS FOR THE BUILDING DESIGN STANDARDS FOR TOWNHouses FOUND IN SECTION 2.01.03.06.019(P) OF THE CITY OF ZEPHYRHILLS LAND DEVELOPMENT CODE. PRIOR TO SUBMITTING FOR BUILDING PERMITS, THE OWNER/DEVELOPER SHALL SUBMIT BUILDING ELEVATIONS TO THE PLANNING DEPARTMENT TO DEMONSTRATE THAT THE BLDGS COMPLY WITH THESE STANDARDS. THESE BUILDING ELEVATIONS SHALL BE REVIEWED AND APPROVED BY THE PLANNING DEPARTMENT PRIOR TO SUBMITTAL OF THE BUILDING PERMITS.



**MASER**  
CONSULTING P.A.  
Customer Loyalty through Client Satisfaction  
www.maserconsulting.com  
Office Locations:  
■ NEW JERSEY ■ NEW MEXICO  
■ NEW YORK ■ MARYLAND ■ GEORGIA  
■ VIRGINIA ■ TEXAS ■ FLORIDA ■ TENNESSEE  
■ NORTH CAROLINA ■ COLORADO  
State of F.L. C.O.A.: 30301 / LB7388

Copyright © 2021, Maser Consulting. All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the individual or entity to whom it is directed and is not to be copied or distributed. This drawing may not be copied, reproduced, disclosed, distributed or copied for any other purpose without the express written consent of Maser Consulting, P.A.

**811**  
Protect Yourself  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE  
Know who's below.  
Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

#### TABLE OF BULK REQUIREMENTS ZONE: MULTI-FAMILY RESIDENTIAL (R-3)

ITEM	REQUIRED	PROVIDED	COMPLIES
MIN. LOT AREA	1,700 S.F.	1,854 S.F.	YES
MIN. LOT WIDTH	17'	18'	YES
MIN. FRONT YARD SETBACK	SEE FRONT YARD SETBACK NOTES	15'	YES
SIDE YARD SETBACK	SEE SETBACK NOTES	10'	N/A
REAR YARD SETBACK	20'	20'	YES
MAX. BUILDING HEIGHT	35'	<35'	YES
BUILDING (LOT) COVERAGE	80%	59%	YES

#### GENERAL DESIGN & REFERENCE NOTES:

- EXISTING INFORMATION SHOWN HEREON AS APPROXIMATE AND IS TAKEN FROM A SURVEY TITLED "BOUNDARY, TOPOGRAPHIC AND TREE SURVEY" PREPARED BY MASER CONSULTING, DATED NOVEMBER 22, 2019.
- THE HORIZONTAL AND VERTICAL DATUM ARE PER ABOVE REFERENCED SURVEY. ELEVATIONS DERIVED FROM NGS BENCHMARK "C 663", PASCO COUNTY FLORIDA, ELEVATION 81.57 (NAVD 88).
- THE PARCEL SHOWN HEREON LIES IN FLOOD ZONE "X" PER THE FLOOD INSURANCE RATE MAP FOR PASCO COUNTY, FLORIDA PER MAP NUMBER I2101C052F, WITH AN EFFECTIVE DATE OF SEPTEMBER 26, 2014 AS ESTABLISHED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA).
- WATER AND SANITARY SEWER SERVICES WILL BE PROVIDED BY THE CITY OF ZEPHYRHILLS UTILITIES DEPARTMENT.
- THE PROJECT WILL UTILIZE A PRESSURE SEWER AND LIFT STATION TO CONNECT TO EXISTING MANHOLE ON LAWANDA LOOP GRAVITY SEWER TO LIFT STATION.
- THE MAXIMUM WATER DEMAND FOR THE DEVELOPMENT WILL BE (300 GPD X 64 UNITS = 19,200 GPD \* 4.0 (PEAKING FACTOR) = 76,800 GPD)
- THERE ARE NO STATE, LOCAL, OR SWFWMD WETLANDS IN THE PROXIMITY OF THE PROPOSED DEVELOPMENT.
- STORMWATER INFORMATION:
  - PRE-DEVELOPED CN FOR THE PROJECT SITE IS 43, SCS SOIL TYPE A.
  - PRE-DEVELOPMENT IMPERVIOUS AREA IS ± 0 SF.
- FIRE PROTECTION PROVIDED BY CITY OF ZEPHYRHILLS FIRE DEPT. VIA PROPOSED FIRE HYDRANTS.
- ALL PROPOSED SIGNS MUST BE APPLIED FOR, APPROVED AND PERMITTED ON AN INDIVIDUAL BASIS APART FROM ANY ULTIMATELY APPROVED SITE PLAN.
- ALL CLEAR-SITE AREAS SHALL BE KEPT FREE OF ANY SIGNAGE, PLANTINGS, OR STATE RIGHT-OF-WAY WITHOUT ISSUANCE OF APPROPRIATE RIGHT-OF-WAY USE PERMIT.
- PROPOSED CONCRETE PAVING AND SIDEWALKS AS NOTED.
- SOIL TYPES: PER SOIL SURVEY OF PASCO COUNTY, FLORIDA SHEET NO. 49 THE SOILS ARE TAVARES, MILLHOPPER AND NEWMAN.
- FUGITIVE DUST SHALL BE CONTROLLED BY SPRINKLING DURING CONSTRUCTION IF REQUIRED.
- HANDICAPPED PARKING SPACES WILL BE PROPERLY SIGNED AND STRIPED IN ACCORDANCE WITH FLORIDA STATUTE 316.116 THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, OR OTHER APPLICABLE STANDARDS.
- PAVEMENT MARKINGS IN DRIVEWAY SHALL BE PER FDOT INDEX NO. 711-001.
- ALL DISTURBED AREAS WITHIN PASCO R.O.W. SHALL BE SODDED.
- DRIVEWAYS SHALL CONFORM TO FOOT INDEX NO. 330-001.
- SITE CONTRACTOR TO VERIFY ALL UTILITY CONNECTION TO BUILDING WITH THE ARCHITECT PRIOR TO STARTING CONSTRUCTION.
- THE ARCHITECT/ENGINEER CERTIFIES THAT THE SITE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT.
- ALL ON-SITE PARKING SPACES WILL BE STRIPED AND SIGNED IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION PARKING SPACES, DIRECTIONAL ARROWS, AND STOP BARS SHALL BE STRIPED IN WHITE. IT SHALL BE THE OWNER/DEVELOPER'S RESPONSIBILITY TO PROPERLY SIGN AND STRIPE THE SITE IN ACCORDANCE WITH APPLICABLE STANDARDS.
- THE OWNER/DEVELOPER ACKNOWLEDGES THAT THIS APPROVAL DOES NOT INCLUDE ANY WORK IN COUNTY R.O.W. ALL RIGHT OF WAY WORK SHALL BE A FUNCTION OF AN APPROVED PASCO COUNTY RIGHT OF WAY USE PERMIT.
- ALL STRUCTURES, INCLUDING BUFFER WALLS, RETAINING WALLS, SIGNAGE ETC. REQUIRE A SEPARATE BUILDING PERMITS.
- NO ON-SITE BURNING IS PROPOSED. IF SO SEPARATE FIRE MARSHALL APPROVAL IS REQUIRED.
- ALL CONSTRUCTION IN COUNTY R.O.W. SHALL CONFORM TO CURRENT PASCO COUNTY SPECIFICATIONS.
- RETENTION AREAS TO BE MAINTAINED BY OWNERS.
- EXISTING VEGETATION IS TREES AND UNDERBRUSH.
- THE OWNER/DEVELOPER ACKNOWLEDGE THAT THE SITE AND ITS SUBSEQUENT BUILDING PERMITS SHALL COMPLY WITH ALL ZONING CONDITIONS.
- AN OPEN SPACE AMENITY AREA SHALL BE PROVIDED IN ACCORDANCE WITH THE CITY OF ZEPHYRHILLS TOWNHOUSE DEVELOPMENT STANDARDS. AT A MINIMUM, THE AMENITY AREAS SHALL INCLUDE A PLAYGROUND, PICNIC SHELTER & SHUFFLEBOARD.
- PLAYGROUND EQUIPMENT SHALL BE CERTIFIED BY INTERNATIONAL PLAY EQUIPMENT MANUFACTURERS ASSOCIATION (IPEMA) UTILIZING CURRENT AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) STANDARD F1487. PLAYGROUND SURFACE SHALL MEET CURRENT ASTM (F1487) STANDARDS
- ALL STREETS SHALL BE PRIVATE.
- SOLID WASTE PICK-UP WILL BE CURBSIDE FOR EACH UNIT.
- BUILDINGS ARE PROPOSED TO BE SINGLE-STORY.
- NO LOTS ARE LOCATED WITHIN A FLOOD ZONE.
- STREETS, DRAINAGE AND UTILITIES ARE PRIVATE.

#### SETBACK NOTES


BUILDING WALL MINIMUM DISTANCE  
FRONT: 15 FEET FROM FRONT FAÇADE WALL  
20 FEET FROM FRONT OF GARAGE WALL  
SIDE: 15 FEET FROM INTERIOR ROADWAY OR PARKING AREA  
10 FEET FROM EDGE OF A RECREATION AMENITY  
10 FEET FROM EDGE OF A STORM WATER RETENTION OR DETENTION AREA

#### PARKING AND LOADING

PARKING:  
REQUIRED: TOWNHOMES 2 SPACE PER UNIT  
(94 UNITS X 2) = 188 SPACES  
ADA PARKING SPACES REQUIRED: 1 SPACES  
ADA PARKING SPACES PROVIDED: 1 SPACES  
PROVIDED: 94 GARAGE SPACES  
94 DRIVEWAY SPACES  
24 GUEST SPACES  
274 TOTAL SPACES  
PARKING STALL SIZE: 9' X 20' REQUIRED  
9' X 20' PROVIDED  
8' X 23' REQUIRED PARALLEL PARKING  
8' X 23' PROVIDED

#### OPEN SPACE CALCULATION

PARENT TRACT = 9.82 AC  
R/W DEDICATION TO PASCO COUNTY = 0.08 AC  
NET PROJECT AREA = 9.74 AC  
REQUIRED OPEN SPACE (30% OF 9.74 AC) = 2.92 AC  
OPEN SPACE PROVIDED = 2.92 AC



**STUART ROGERS**  
FLORIDA PROFESSIONAL  
ENGINEER - LICENSE NUMBER: 42718

#### PRELIMINARY PLAT & IMPROVEMENT PLAN FOR AUTUMN PALM DRIVE, LLC

PARCEL ID:  
15-26-21-0030-08100-0010

CITY OF ZEPHYRHILLS  
PASCO COUNTY  
FLORIDA


TAMPA OFFICE  
5471 West Waters Avenue  
Suite 100  
Tampa, FL 33634  
Phone: 813.207.1061  
Fax: 813.281.1050

SCALE: AS SHOWN DATE: 12/31/19 DRAWN BY: SMR CHECKED BY:  
PROJECT NUMBER: 19002495A DRAWN BY: SMR  
SHEET TITLE: AUTUMN PALM 18' UNITS LENNAR  
SHEET NUMBER: 3 of 21

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION.  
4/27/2021 3:42:15 PM

## MAPS


## Location Map



Aerial




## Future Land Use Map - Pasco County




Note: all areas in purple are Pasco County Residential - 9

## Current Zoning Map – Pasco County



## Current Future Land Use Map – City



## Current Zoning Map – City

